



FREDERICK COUNTY GOVERNMENT

Jan H. Gardner
County Executive

DIVISION OF FINANCE

Department of Procurement & Contracting

Lori L. Depies, CPA, Division Director
Diane Fouche, CPPB, Director

May 17, 2018

IFB No. 18-363-CP

MYERSVILLE LIBRARY

Addendum No. 4

This addendum contains revisions, clarifications, and information pertinent to the IFB for the referenced project and shall supplement, amend, and become part of the IFB for the title project and contract. All bids shall be based on this Addendum, in accordance with the IFB documents.

Acknowledgment of this addendum shall be submitted with the bid, including addendum number and date. Failure to acknowledge addendum may subject the contractor to disqualification.

Bids are due May 22, 2018 before 2:00 PM EST.

CHANGES TO THE DRAWINGS:

1. Sheet C-12 – Stormwater Management Notes and Details

Micro-Bioretenion Area Dimensions-

Delete elevations listed under Column F and replace with the following: "671.0, 671.0, and 673.0".

Delete numbers listed under Column I and replace with the following: "3.0, 3.0, and 3.0".

2. Sheet I000 – Finish Schedule and Finish Plans

Finish Schedule:

100 Vestibule- Ceiling Material- Delete designation and replace with "ACT-1/P-3";
Remarks- Add "7".

105 Custodial- Ceiling Material- Delete designation and replace with "P-1".

105A Custodial- Ceiling Material- Delete designation and replace with "P-1".

108 Desk- Ceiling Material- Delete designation and replace with "ACT-1/P-3/P-5".

109 Children's Area- Ceiling Material- Delete designation and replace with "C-1/P-3".

110 Stacks- Ceiling Material- Delete designation and replace with "C-1/ACT-1/P-3".

119 Study Area- Ceiling Material- Delete designation and replace with "ACT-1/P-3".

121 Mech/Elec- Ceiling Material- Delete designation and replace with "P-1".

200 Mech. Loft- Flooring- Add "Seal.Conc."; Walls (all)- Add "P-1"; Ceiling Material- Add "P-1".

Frederick County: Rich History, Bright Future

Myersville Library
IFB No. 18-363-CP
Addendum No. 4

Finish Notes- Add the following note:

"7. Paint drywall ceiling P-3. Ceiling of passage to restrooms shall be ACT-1".

3. Sheet I000 – Finish Schedule and Finish Plans

Finish Schedule:

Drawing 3-1000, Finish and Floor Pattern Plan: Add the following note to Children's Area 109: "The full width of the transitional border tile (CPT-1) shall be centered on the border line and cut as required to follow the meandering curve. Field tiles (CPT-2 and CPT-3) shall be laid out in an orthogonal pattern on either side of the full width transitional border tile and cut as required to fit the transitional border curve. Refer to specs for shop drawing requirements".

END OF ADDENDUM

Except as noted herein, all terms and conditions of the document referenced, as heretofore changed, remain unchanged and in full force and effect.



Bruce Johnson
Project Manager IV